

Draft BOQ — unpriced

Sattva Court



Vextrus Cubit

Project	Sattva Court
Client	Sattva Developments Ltd.
Site	Plot 12, Road 4, Sector 7, Uttara, Dhaka
Drawing set	Sattva Court structural set, revision 2, pinned 20 Sep 2026
Drawings	sattva-court-structural.dxf, sattva-court-architectural.dxf
Issued	24 Sep 2026
Sections	By the taxonomy of 16 Sep 2026
Measurement	Incomplete: what this draft leaves out is listed under Not measured in this draft

PREPARED BY

Name

Date

CHECKED BY

Name

Date

1 Substructure

ITEM	DESCRIPTION	LEVEL	QUANTITY	UNIT
COLUMN · CONCRETE				
1.1.1	Reinforced cement concrete cast in place, measured net of its reinforcement — columns	FDN	0.810	m3
COLUMN · REBAR				
1.2.1	Reinforcement steel in place, measured as nominal mass with laps billed beside the net — columns, fy 500 MPa (None of 2 measured — note reading contested; rebar tie zone unstated)	FDN	Not measured	kg
PILE CAP · CONCRETE				
1.3.1	Reinforced cement concrete cast in place, measured net of its reinforcement — pile caps	FDN	8.321	m3
PILE CAP · FORMWORK				
1.4.1	Formwork to reinforced cement concrete, measured as the contact area of the cast face — pile caps	FDN	9.75	m2
PILE CAP · BLINDING				
1.5.1	Plain cement concrete blinding under foundations, measured as the laid volume — pile caps, thickness 3 in (1 of 2 measured; 1 not measured — blinding plan deferred)	FDN	0.391	m3

ITEM	DESCRIPTION	LEVEL	QUANTITY	UNIT
PILE · CONCRETE				
1.6.1	Reinforced cement concrete cast in place, measured net of its reinforcement — piles, diameter 500 mm	Foundation	8.379	m3

2 Superstructure

ITEM	DESCRIPTION	LEVEL	QUANTITY	UNIT
COLUMN · CONCRETE				
2.1.1	Reinforced cement concrete cast in place, measured net of its reinforcement — columns	GF	0.810	m3
2.1.2	Reinforced cement concrete cast in place, measured net of its reinforcement — columns	1F	0.366	m3
COLUMN · FORMWORK				
2.2.1	Formwork to reinforced cement concrete, measured as the contact area of the cast face — columns	GF	6.48	m2
BEAM · CONCRETE				
2.3.1	Reinforced cement concrete cast in place, measured net of its reinforcement — beams	GF	1.296	m3
SLAB · CONCRETE				
2.4.1	Reinforced cement concrete cast in place, measured net of its reinforcement — slabs	1F	12.480	m3
BRICK WALL · BRICKWORK				
2.5.1	Brickwork in walls, measured as the wall face net of scheduled openings by its nominal thickness — brick walls	1F	8.640	m3

3 Finishes

ITEM	DESCRIPTION	LEVEL	QUANTITY	UNIT
SURFACE · PLASTER				
3.1.1	Plaster to surfaces, measured as the finished face net of scheduled openings — surfaces	1F	24.50	m2
SURFACE · PAINT				
3.2.1	Paint to surfaces, measured as the painted face net of scheduled openings — surfaces (None of 1 measured — opening schedule absent)	1F	Not measured	m2

Unclassified

REASON	DESCRIPTION	LEVEL	QUANTITY	UNIT
Level not in stack	Column · Concrete		0.324	m3

Not measured in this draft

Scope no line was published for

DESCRIPTION	LEVELS	WHY
Boring		No class sighted in this campaign bears this kind, so no cell stands for it.
Slab · Concrete	GF–2F	No line has been published for this kind on this class and level, and nothing explains the absence.
Stair · Concrete	GF	A person declared this kind out of the project scope on this class and level.

Why a line states no figure

REASON	WHAT IT MEANS
Note reading contested	Two readings of this note disagree, so no figure stands.
Rebar tie zone unstated	The schedule states the tie spacing for this member but no zone it runs over, so its ties cannot be counted.
Blinding plan deferred	This foundation's plan is not a rectangle, and the blinding under a non-rectangular plan is not measured yet.
Opening schedule absent	No opening schedule stands behind this face, so it is not measured — its gross area would over-measure the work.

Details of measurement

Each item states the register's sum of its members, rounded once to the places its kind is written to. Each member line below states its own register figure, rounded once the same way.

1.1.1 Reinforced cement concrete cast in place, measured net of its reinforcement — columns · FDN

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
C1	A/1	FDN	1	L 0.45 m · B 0.45 m · H 4 m	0.810	m3	Measured	S-04

1.2.1 Reinforcement steel in place, measured as nominal mass with laps billed beside the net — columns, fy 500 MPa · FDN

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
C1	A/1	FDN		net 117.46992 kg · lap not stated · ties not stated	Not measured	kg	Derived	S-04
C2	B/1	FDN		net 98.1 kg · lap not stated · ties not stated	Not measured	kg	Derived	S-04

1.3.1 Reinforced cement concrete cast in place, measured net of its reinforcement — pile caps · FDN

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
PC1	A/1	FDN	1	L 2 m · B 1.6 m · D 1.3002 m	4.160	m3	Measured	S-06
PC2	B/1	FDN	1	L 2 m · B 1.6 m · D 1.3002 m	4.160	m3	Measured	S-06

1.4.1 Formwork to reinforced cement concrete, measured as the contact area of the cast face — pile caps · FDN

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
PC1	A/1	FDN	1	L 2 m · B 1.75 m · D 1.3 m	9.75	m2	Measured	S-06

1.5.1 Plain cement concrete blinding under foundations, measured as the laid volume — pile caps, thickness 3 in · FDN

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
PC1	A/1	FDN	1	L 2 m · p 0.0762 m · B 1 m · t 0.0762 m	0.391	m3	Measured	S-06
PC2	B/1	FDN	1	L not stated · p 0.0762 m · B not stated · t 0.0762 m	Not measured	m3	Derived	S-06

1.6.1 Reinforced cement concrete cast in place, measured net of its reinforcement — piles, diameter 500 mm · Foundation

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
P1	A/1	Foundation	1	d 0.5 m · length 21.336 m	4.189	m3	Measured	S-05
P2	B/1	Foundation	1	d 0.5 m · length 21.336 m	4.189	m3	Measured	S-05

2.1.1 Reinforced cement concrete cast in place, measured net of its reinforcement — columns · GF

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
C1	A/1	GF	1	L 0.45 m · B 0.3 m · H 3 m	0.405	m3	Measured	S-10
C2	B/1	GF	1	L 0.45 m · B 0.3 m · H 3 m	0.405	m3	Measured	S-10

2.1.2 Reinforced cement concrete cast in place, measured net of its reinforcement — columns · 1F

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
C1	A/1	1F	1	L 0.4 m · B 0.3 m · H 3.048 m	0.366	m3	Measured	S-11

2.2.1 Formwork to reinforced cement concrete, measured as the contact area of the cast face — columns · GF

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
C2	B/1	GF	1	L 0.6 m · B 0.48 m · H 3 m	6.48	m2	Measured	S-10

2.3.1 Reinforced cement concrete cast in place, measured net of its reinforcement — beams · GF

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
B1		GF	1	b 0.3 m · D 0.6 m · clear 7.2 m	1.296	m3	Measured	S-12

2.4.1 Reinforced cement concrete cast in place, measured net of its reinforcement — slabs · 1F

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
S1		1F	1	A 83.2 m2 · t 0.15 m	12.480	m3	Measured	S-13

2.5.1 Brickwork in walls, measured as the wall face net of scheduled openings by its nominal thickness — brick walls · 1F

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
W1		1F	1	L 12 m · H 2.88 m · t 0.25 m	8.640	m3	Measured	A-02

3.1.1 Plaster to surfaces, measured as the finished face net of scheduled openings — surfaces · 1F

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
F1		1F	1	L 8.75 m · H 2.8 m	24.50	m2	Measured	A-02

3.2.1 Paint to surfaces, measured as the painted face net of scheduled openings — surfaces · 1F

MARK	GRID	LEVEL	NOS	DIMENSIONS	QUANTITY	UNIT	BASIS	SHEET
F1		1F	1	L 8.75 m · H 2.8 m · openings not stated	Not measured	m2	Derived	A-02